



Solano County Water Agency

Lower Putah Creek Riparian Water Availability Forecast: Mar. 1, 2017
(Projected water availability in the absence of Monticello Dam)

Reach No. 4: Hwy. 180 Bridge to Mace Boulevard Bridge

Average Monthly Flow in Cubic Feet Per Second (cfs)
(projected stream flow at downstream end of reach)

Percent Exceedance	Apr	May	Jun	Jul	Aug	Sep	Oct
5%	2,028	553	171	70	35	13	50
10%	1,249	395	122	54	8	0	30
15%	909	318	94	44	1	0	6
20%	793	235	81	31	0	0	0
25%	662	190	68	22	0	0	0
30%	487	170	53	12	0	0	0
35%	418	145	44	0	0	0	0
40%	359	130	39	0	0	0	0
45%	284	119	33	0	0	0	0
50%	261	113	28	0	0	0	0
55%	230	86	21	0	0	0	0
60%	196	75	8	0	0	0	0
65%	186	62	0	0	0	0	0
70%	155	51	0	0	0	0	0
75%	142	47	0	0	0	0	0
80%	109	33	0	0	0	0	0
85%	76	26	0	0	0	0	0
90%	60	7	0	0	0	0	0
95%	35	1	0	0	0	0	0
100%	0	0	0	0	0	0	0