



Solano County Water Agency

Lower Putah Creek Riparian Water Availability Forecast: May 1, 2017
(Projected water availability in the absence of Monticello Dam)

Reach No. 2: Hwy. 505 Bridge to Stevenson Road Bridge

Average Monthly Flow in Cubic Feet Per Second (cfs)
(projected stream flow at downstream end of reach)

Percent Exceedance	Apr	May	Jun	Jul	Aug	Sep	Oct
5%	NA	560	204	95	64	23	66
10%	NA	408	161	85	40	15	50
15%	NA	336	135	78	35	11	29
20%	NA	256	126	68	28	7	21
25%	NA	213	114	60	25	4	17
30%	NA	195	101	51	19	2	12
35%	NA	170	92	39	17	1	9
40%	NA	157	88	33	16	0	8
45%	NA	147	83	31	15	0	8
50%	NA	141	78	28	13	0	8
55%	NA	115	72	26	12	0	8
60%	NA	105	59	24	10	0	8
65%	NA	92	51	22	8	0	8
70%	NA	82	45	19	4	0	8
75%	NA	78	43	16	4	0	8
80%	NA	65	37	9	4	0	8
85%	NA	58	31	7	4	0	8
90%	NA	40	26	7	4	0	8
95%	NA	34	18	7	3	0	8
100%	NA	15	18	7	3	0	8