



Solano County Water Agency

Lower Putah Creek Riparian Water Availability Forecast: May 1, 2017
(Projected water availability in the absence of Monticello Dam)

Reach No. 3: Stevenson Road Bridge to Hwy. 180 Bridge

Average Monthly Flow in Cubic Feet Per Second (cfs)
(projected stream flow at downstream end of reach)

Percent Exceedance	Apr	May	Jun	Jul	Aug	Sep	Oct
5%	NA	571	202	104	52	28	76
10%	NA	420	159	94	28	20	59
15%	NA	347	134	87	23	16	38
20%	NA	267	124	76	16	12	30
25%	NA	225	113	69	13	9	26
30%	NA	206	99	60	7	7	21
35%	NA	182	91	48	5	6	18
40%	NA	168	86	42	4	5	17
45%	NA	158	81	39	3	5	17
50%	NA	152	77	37	1	5	17
55%	NA	126	70	35	0	5	17
60%	NA	116	58	33	0	5	17
65%	NA	103	49	31	0	5	17
70%	NA	93	43	28	0	5	17
75%	NA	89	41	24	0	5	17
80%	NA	76	35	17	0	5	17
85%	NA	69	29	16	0	5	17
90%	NA	51	25	16	0	5	17
95%	NA	45	16	16	0	5	17
100%	NA	27	16	16	0	5	17