



Solano County Water Agency

Lower Putah Creek Riparian Water Availability Forecast: May 1, 2017
(Projected water availability in the absence of Monticello Dam)

Reach No. 5: Mace Blvd. Bridge to River Mile 0.0 of Putah Creek

Average Monthly Flow in Cubic Feet Per Second (cfs)
(projected stream flow at downstream end of reach)

Percent Exceedance	Apr	May	Jun	Jul	Aug	Sep	Oct
5%	NA	566	200	102	50	26	74
10%	NA	414	157	91	26	17	58
15%	NA	342	131	85	20	13	36
20%	NA	262	121	74	14	9	28
25%	NA	219	110	66	10	7	24
30%	NA	201	96	57	5	5	19
35%	NA	177	88	45	3	3	15
40%	NA	163	83	40	1	2	15
45%	NA	153	78	37	0	2	15
50%	NA	147	74	34	0	2	15
55%	NA	121	67	32	0	2	15
60%	NA	111	55	30	0	2	15
65%	NA	98	47	28	0	2	15
70%	NA	88	40	25	0	2	15
75%	NA	84	39	22	0	2	15
80%	NA	71	32	15	0	2	15
85%	NA	64	27	13	0	2	15
90%	NA	46	22	13	0	2	14
95%	NA	40	13	13	0	2	14
100%	NA	21	13	13	0	2	14