



Solano County Water Agency

Lower Putah Creek Riparian Water Availability Forecast: Jan. 1, 2018
(Projected water availability in the absence of Monticello Dam)

Reach No. 2: Hwy. 505 Bridge to Stevenson Road Bridge

Average Monthly Gain(-) or Loss(+) in Cubic Feet Per Second (cfs)
(projected Average gain or loss in the reach)

Percent Exceedance	Apr	May	Jun	Jul	Aug	Sep	Oct
5%	-34	-38	-28	-16	-15	-17	-16
10%	-30	-33	-23	-11	-11	-14	-12
15%	-28	-30	-21	-9	-10	-13	-10
20%	-26	-28	-18	-7	-8	-12	-9
25%	-25	-26	-17	-6	-7	-12	-8
30%	-23	-24	-15	-4	-6	-11	-7
35%	-22	-23	-14	-4	-5	-11	-7
40%	-21	-22	-13	-3	-5	-10	-6
45%	-20	-21	-12	-2	-4	-10	-6
50%	-19	-20	-11	-1	-4	-10	-5
55%	-19	-19	-10	-1	-3	-10	-5
60%	-18	-18	-10	0	-3	-9	-4
65%	-18	-18	-9	0	-3	-9	-4
70%	-17	-17	-9	0	-2	-9	-4
75%	-17	-16	-8	1	-2	-9	-4
80%	-16	-16	-8	1	-2	-9	-3
85%	-16	-15	-7	2	-2	-9	-3
90%	-15	-15	-7	2	-1	-8	-3
95%	-15	-15	-7	2	-1	-8	-3
100%	-15	-14	-6	2	-1	-8	-3