



Solano County Water Agency

Lower Putah Creek Riparian Water Availability Forecast: Jan. 1, 2018
(Projected water availability in the absence of Monticello Dam)

Reach No. 1: Putah Diversion Dam to Hwy. 505 Bridge

Average Monthly Flow in Cubic Feet Per Second (cfs)
(projected stream flow at downstream end of reach)

Percent Exceedance	Apr	May	Jun	Jul	Aug	Sep	Oct
5%	2,034	552	184	82	57	32	59
10%	1,255	404	138	69	31	22	41
15%	936	327	110	61	25	17	19
20%	833	250	100	50	18	13	12
25%	680	207	88	42	15	10	8
30%	513	189	73	31	9	7	3
35%	447	167	63	20	7	6	0
40%	378	153	58	14	5	4	0
45%	304	141	53	11	4	1	0
50%	278	135	47	7	2	0	0
55%	246	110	39	6	0	0	0
60%	209	97	28	4	0	0	0
65%	201	85	20	0	0	0	0
70%	169	74	13	0	0	0	0
75%	157	71	11	0	0	0	0
80%	122	58	5	0	0	0	0
85%	88	51	0	0	0	0	0
90%	73	32	0	0	0	0	0
95%	48	26	0	0	0	0	0
100%	3	7	0	0	0	0	0