



Solano County Water Agency

Lower Putah Creek Riparian Water Availability Forecast: Mar. 1, 2018
(Projected water availability in the absence of Monticello Dam)

Reach No. 2: Hwy. 505 Bridge to Stevenson Road Bridge

Average Monthly Flow in Cubic Feet Per Second (cfs)
(projected stream flow at downstream end of reach)

Percent Exceedance	Apr	May	Jun	Jul	Aug	Sep	Oct
5%	2,038	572	189	81	60	39	65
10%	1,263	423	144	69	35	30	46
15%	945	346	116	61	28	25	24
20%	843	267	106	49	21	20	16
25%	690	224	94	41	17	17	12
30%	524	206	79	30	11	15	7
35%	460	184	70	19	9	14	4
40%	391	169	65	13	7	12	4
45%	318	158	60	9	6	9	4
50%	292	152	55	6	4	9	4
55%	260	126	47	5	2	9	4
60%	224	113	36	3	2	9	4
65%	216	101	27	0	2	9	4
70%	185	90	20	0	2	9	4
75%	173	87	18	0	2	9	3
80%	138	74	13	0	2	9	3
85%	104	67	7	0	2	9	3
90%	89	48	7	0	2	8	3
95%	64	41	7	0	1	8	3
100%	19	22	7	0	1	8	3