



Solano County Water Agency

Lower Putah Creek Riparian Water Availability Forecast: Jan. 1, 2018
(Projected water availability in the absence of Monticello Dam)

Reach No. 2: Hwy. 505 Bridge to Stevenson Road Bridge

Average Monthly Flow in Cubic Feet Per Second (cfs)
(projected stream flow at downstream end of reach)

Percent Exceedance	Apr	May	Jun	Jul	Aug	Sep	Oct
5%	2,068	590	212	98	72	49	74
10%	1,285	437	161	80	43	36	52
15%	964	358	131	70	35	31	30
20%	859	277	118	57	26	25	21
25%	704	233	105	48	22	21	16
30%	536	213	88	36	15	18	10
35%	469	190	77	23	12	16	7
40%	399	175	71	16	9	14	6
45%	324	162	65	13	8	11	6
50%	297	155	58	9	6	10	5
55%	265	129	50	6	4	10	5
60%	228	116	38	4	3	9	4
65%	219	103	29	0	3	9	4
70%	187	92	21	0	2	9	4
75%	174	87	19	0	2	9	4
80%	138	74	13	0	2	9	3
85%	104	66	7	0	2	9	3
90%	88	47	7	0	1	8	3
95%	63	41	7	0	1	8	3
100%	18	21	6	0	1	8	3