



Solano County Water Agency

Lower Putah Creek Riparian Water Availability Forecast: Jan. 1, 2018
(Projected water availability in the absence of Monticello Dam)

Reach No. 3: Stevenson Road Bridge to Hwy. 180 Bridge

Average Monthly Flow in Cubic Feet Per Second (cfs)
(projected stream flow at downstream end of reach)

Percent Exceedance	Apr	May	Jun	Jul	Aug	Sep	Oct
5%	2,090	614	219	125	42	63	100
10%	1,304	457	166	104	14	46	75
15%	983	377	135	93	7	39	52
20%	876	295	122	78	0	32	41
25%	722	250	108	69	0	27	36
30%	553	230	91	56	0	23	30
35%	486	206	80	43	0	21	26
40%	415	190	74	36	0	17	25
45%	340	177	68	31	0	14	24
50%	313	169	61	27	0	12	23
55%	280	143	53	25	0	12	22
60%	243	130	41	22	0	11	22
65%	234	116	32	18	0	11	21
70%	202	105	24	18	0	10	21
75%	189	100	21	17	0	10	20
80%	153	87	15	17	0	9	20
85%	119	79	9	17	0	9	20
90%	103	59	9	17	0	9	19
95%	78	53	9	17	0	8	19
100%	32	33	8	17	0	8	19