



Solano County Water Agency

Lower Putah Creek Riparian Water Availability Forecast: Mar. 1, 2018
(Projected water availability in the absence of Monticello Dam)

Reach No. 4: Hwy. 180 Bridge to Mace Boulevard Bridge

Average Monthly Flow in Cubic Feet Per Second (cfs)
(projected stream flow at downstream end of reach)

Percent Exceedance	Apr	May	Jun	Jul	Aug	Sep	Oct
5%	2,049	583	188	97	28	39	79
10%	1,273	432	141	82	2	27	59
15%	955	354	113	73	0	21	36
20%	852	274	102	60	0	16	27
25%	699	230	89	51	0	12	22
30%	533	212	74	40	0	9	17
35%	468	189	65	29	0	8	14
40%	400	175	60	22	0	5	14
45%	326	163	54	19	0	3	13
50%	300	157	49	16	0	2	13
55%	269	131	41	14	0	2	13
60%	232	118	30	12	0	1	12
65%	224	106	21	9	0	1	12
70%	193	95	14	9	0	1	12
75%	181	91	12	9	0	1	12
80%	146	78	6	8	0	0	11
85%	112	71	1	8	0	0	11
90%	97	52	1	8	0	0	11
95%	72	46	1	8	0	0	11
100%	27	26	0	8	0	0	11