



Solano County Water Agency

Lower Putah Creek Riparian Water Availability Forecast: Jan. 1, 2018
(Projected water availability in the absence of Monticello Dam)

Reach No. 4: Hwy. 180 Bridge to Mace Boulevard Bridge

Average Monthly Flow in Cubic Feet Per Second (cfs)
(projected stream flow at downstream end of reach)

Percent Exceedance	Apr	May	Jun	Jul	Aug	Sep	Oct
5%	2,089	613	220	126	43	64	101
10%	1,301	454	164	102	12	44	73
15%	979	373	132	90	4	36	48
20%	872	290	118	74	0	27	37
25%	717	245	103	64	0	22	31
30%	547	223	86	50	0	17	24
35%	481	199	74	37	0	14	19
40%	410	183	67	29	0	11	18
45%	334	170	60	24	0	7	17
50%	307	162	54	20	0	5	16
55%	274	135	45	17	0	4	15
60%	237	122	33	14	0	3	14
65%	227	108	23	10	0	3	13
70%	195	97	16	9	0	2	13
75%	182	92	13	9	0	1	12
80%	146	78	6	8	0	1	11
85%	112	71	1	8	0	0	11
90%	96	51	0	8	0	0	10
95%	70	44	0	8	0	0	10
100%	25	25	0	7	0	0	10