



Solano County Water Agency

Lower Putah Creek Riparian Water Availability Forecast: May 1, 2018
(Projected water availability in the absence of Monticello Dam)

Reach No. 3: Stevenson Road Bridge to Hwy. 180 Bridge

Average Monthly Flow in Cubic Feet Per Second (cfs)
(projected stream flow at downstream end of reach)

Percent Exceedance	Apr	May	Jun	Jul	Aug	Sep	Oct
5%	NA	576	182	93	30	37	79
10%	NA	430	140	82	6	29	61
15%	NA	354	114	75	1	25	40
20%	NA	278	106	65	0	21	33
25%	NA	235	95	57	0	18	29
30%	NA	218	81	47	0	16	24
35%	NA	196	72	36	0	15	21
40%	NA	182	67	30	0	13	21
45%	NA	171	63	28	0	11	21
50%	NA	165	58	25	0	10	21
55%	NA	140	50	23	0	10	21
60%	NA	128	40	21	0	10	21
65%	NA	115	32	18	0	10	21
70%	NA	105	25	18	0	10	21
75%	NA	102	23	18	0	10	21
80%	NA	89	18	18	0	10	21
85%	NA	82	11	18	0	10	21
90%	NA	63	11	18	0	10	21
95%	NA	57	11	18	0	10	21
100%	NA	38	11	18	0	10	21